

MAK & SONS CONSTRUCTION

Project Timeline: Approx. 4 Months

GRAY STRUCTURE – SCOPE OF WORK

1. FOUNDATION

- 1.1 Excavation: Foundation excavation up to 3.5 ft depth from NSL.
- 1.2 Lean: Brick ballast lean in foundations.
- 1.3 Brickwork in Foundations:
 - 1.3.1 First step: 27"
 - 1.3.2 Second step: 22.5"
 - 1.3.3 Third step: 18"
 - 1.3.4 Fourth step: 13.5"
 - 1.3.5 Remaining up to DPC: 9"
- 1.4 DPC: 3" vertical DPC for maximum seepage protection.
- 1.5 Backfilling: Ghassu backfilling with water settling to prevent cracks.
- 1.6 DPC Waterproofing: Bitumen layer with polythene sheet on DPC.
- 1.7 Plinth Beam: PKR 175/sq.ft. additional (PKR 350/sq.ft. for single-story).
- 1.8 Garage DPC: Double DPC for the garage area.
- 1.9 Termite Spray: Owner's responsibility for ground floor.

2. MASONRY (BRICKWORK)

- 2.1 Complete Brickwork: 9" walls (1:5 ratio).
- 2.2 Partition Brickwork: 4.5" partition walls (1:4 ratio).
- 2.3 Alignment: Checked via water level tool and plumbline.
- 2.4 Curing: Proper and thorough curing for wall strength.

3. LINTEL, SHUTTERING & PLASTER

- 3.1 Shuttering: Wooden shuttering.
- 3.2 Steel: 8x8 steel grid (3 & 4 sootar).
- 3.3 Concealed Beams: Provided on the roof as required.
- 3.4 RCC Lintel: 5" thickness concrete slab (1:2:4 ratio).
- 3.5 Roof Height: 10.5 ft (per society provisions).
- 3.6 Wall Plaster: Inside & outside (1:4 ratio).
- 3.7 Ceiling Plaster: Under-ceiling plaster is not included.
- 3.8 Chapti Plaster: Leveled plaster for perfect symmetry.
- 3.9 Continuous Curing: Continuous Tarai after plastering.

4. ELECTRICAL

- 4.1 Piping: Concealed electrical piping work.

5. RAW FLOOR (KATCHA)

- 5.1 PCC: 1.5" thickness (1:2:4 ratio).
- 5.2 Compactor: Machine used for optimal floor settling.
- 5.3 Termite Spray: Owner's responsibility for ground floor.

6. SANITARY

- 6.1 Sewerage: Sanitary sewerage piping.
- 6.2 Pipe Brand: Dura or Popular brand.
- 6.3 Underground Pipes: Covered with PCC.
- 6.4 Strength: Pipes covered with brick ballast then concrete

7. ROOF, PARAPETS & WATERPROOFING

- 7.1 Parapets: 3 ft high brickwork from the roof slab.
- 7.2 Waterproofing: Roof waterproofing (with marble).

8. CHOWKATS (DOOR FRAMES)

- 8.1 Details: 16-gauge galvanized (Jasti) frames.
- 8.2 Height: 8 ft standard height.

9. SLABS

- 9.1 Kitchen Slab: Concrete kitchen slab.
- 9.2 Vanity Slab: Washroom vanity slab as required.

10. STAIRS

- 10.1 Concrete Steps: Concrete structure for stairs.

11. WARDROBE BASES

- 11.1 Bases (Tharian): Constructed under wardrobes

12. GATES & WINDOWS

- 12.1 Preparation: Owner's responsibility.
- 12.2 Installation: Contractor's responsibility.

13. COVERED AREA MEASUREMENT

- 13.1 Roofs: Complete measurement of all roofs.
- 13.2 Shades & Pergolas: Added to covered area.
- 13.3 Water Tank: Included with double measurement.

14. ADDITIONAL CHARGES

- 14.1 Basement: PKR 1,200/sq.ft additional.
- 14.2 Single Story: Construction rate increases by PKR 600/ sq.ft.
- 14.3 Plinth Beam: PKR 175/sq.ft (PKR 350 for single-story).
- 14.4 Plot Depth: PKR 75/sq.ft extra for deep plots (PKR 150 for single-story).
- 14.5 Extra Work: Any work outside scope charged separately.

GRAY STRUCTURE
PKR 2,950 per sq. ft.

MATERIAL BRANDS

- Brick: First-class (Awwal)
- Cement: Bestway, Lucky, or Flying
- Crush: Sargodha plant
- Sanitary Pipe: Popular / Dura
- Steel: Mughal or Madinah (60 Grade)
- Frames: 16-gauge galvanized iron (Jasti)
- Sand: Local sand



NOTE: IMPORTANT TERMS & CONDITIONS

1. Commencement: Work begins on a 3% advance payment.
2. Map Draft: Provided free of charge upon contract agreement.
3. Timeline: Construction timeline is approximately 4 months.
4. Gate & Safety Grill: Gate prep is owner's responsibility (installation by contractor). Safety grill is excluded.
5. Termite Spray: Building termite spray is the owner's responsibility.
6. Ceiling Plaster: Under-ceiling plaster is not included in this rate.
7. The complete measurement of all roofs will be taken.
8. Shades and pergolas will be added to the covered area.
9. Water tanks will be included with double measurement.



PAYMENT SCHEDULE

1.	Advance	3%
2.	Completion of foundation excavation	5%
3.	Completion of Lean / PCC in foundations	7%
4.	Completion of DPC	15%
5.	Brickwork (Ground Floor)	15%
6.	Slab Pouring (Ground Floor)	11%
7.	Brickwork (First Floor)	15%
8.	Slab pouring (First Floor)	11%
9.	Internal plaster (Ground Floor)	4%
10.	Internal plaster (First Floor)	3%
11.	Raw floors (Katcha)	4%
12.	External plaster (2 sides)	3%
13.	External plaster (remaining 2 sides)	3%
14.	Complete finishing of Gray Structure	1%

TOTAL = 100%